

Wolfe Island Cable Crossing and Structures

KINGSTON, ONTARIO



COMPLETION DATE

October 2008

VALUE OF CONTRACT

\$2,700,000.00

OWNER

Canadian Renewable Energy
A division of Canadian Hydro
Developers Inc.
Calgary, Alberta

CONSULTANT

Canadian Projects Ltd.
Cal Christianson P.Eng
403-508-1560



Project Description

DESCRIPTION

Dredging of 650 meters of rock trench, 2 meters wide by 2 meters deep and 250 meters of on-shore rock trench. Placing of HDPE conduits and backfilling of trench after cable laid by Client. Construction of 2 on-shore concrete joint structures for cable termination.

EQUIPMENT

- McNally No. 1 Jack-up Barge
- Tug Paula M
- Cat 345 Backhoe c/w Hydraulic Breaker
- Unifloat Sections – 6 No.
- Loader c/w Forks/Boom

Subcontractors

- T.A. Andre – Concrete Work
- Corcoran – On-shore Earthworks

