

Jetty NH SSP Repair

HALIFAX, NOVA SCOTIA



COMPLETION DATE

December 2008

VALUE OF CONTRACT

\$880,000.00

OWNER

Department of National Defence
(DND)

CONSULTANT

Department of National Defence
(DND)

BEAVER MARINE
LIMITED

Project Description

DESCRIPTION

Construction of a concrete copewall over existing steel sheet pile for berthing face for DND vessels.

EQUIPMENT

Linkbelt LS-108B Crane,
CAT 950 E Loader

INSTALLATION METHOD

Tremie poured concrete copewall over existing steel sheet pile (SSP) wall. Sacrificial anodes installed on SSP by divers. New timber rubbing strips and wheelguard.

