

Salter Street Boardwalk

HALIFAX, NOVA SCOTIA

Salter Street Boardwalk



COMPLETION DATE

May 2009

VALUE OF CONTRACT

\$3,000,000

OWNER

Waterfront Development Corporation Limited

CONSULTANT

O'Halloran Campbell Consultants Limited



Project Description

DESCRIPTION

Construction of timber boardwalk extension along the Halifax waterfront for the Waterfront Development Corporation Limited to allow for the construction of a new building in the future.

EQUIPMENT

“Beaver Kay” Spud Barge,
“Oshawa” Workboat,
Linkbelt LS-518 Crane
Linkbelt LS-108B crane
John Deere 450 excavator
Pile Hammers

INSTALLATION METHOD

The boardwalk structure consists of treated timber deck supported on driven treated timber piles and pipe piles. Pipe piles complete with drilled rock sockets or rock anchors. Timber fender piles, ladders and wheel guard complete the structure.