Ajax Raw Water Intake

LAKE ONTARIO, AJAX, ONTARIO

M^cNALLY

COMPLETION DATE October 1998

VALUE OF CONTRACT \$12,500,000.00

OWNER

Regional Municipality of Durham Contact: Mr. Ken Thompson 905-668-7721

CONSULTANT

Simcoe Engineering Group Ltd. Contact: Mr. Ken Thompson 905-831-1715



T E VECU

Project Description

DESCRIPTION

Installation of 2100 mm Ø Concrete pressure pipe raw water intake - 2520m long in Lake Ontario. Work involved underwater blasting of both rock and very hard till, installation of pipe in trench, intake structure, cofferdam and tunnel on shore. Installation of HDPE chlorine and sample lines in common trench with intake.

EQUIPMENT

Dredge – Derrick No. 1 c/w 200 ton crane, 500 ton stone hopper and conveyor
Derrick No. 4 c/w 2-150mm DHD
Drills
4 cy dipper dredge
Idus Atwell Drill Boat
Tugboat – Bagotville & Paula M.